TOWN OF MAPLEFORD, MASSACHUSETTS

BOARD OF PUBLIC WORKS - WATER DIVISION

CONTRACT DOCUMENTS AND SPECIFICATIONS

ELM STREET AND OAK AVENUE WATER MAIN REPLACEMENT

CONTRACT NO. W-2026-04

SYNTHETIC SAMPLE PACKAGE FOR SOFTWARE TESTING ONLY. This is not a real bid and is not issued by any town. All names, places, dates and quantities are invented.

TABLE OF CONTENTS

Invitation for Bids 3

Instructions to Bidders 4

Bid Form 6

Agreement 9

General Conditions 10

Supplementary Conditions 12

Prevailing Wage Rates 15

Technical Specifications 16

List of Drawings 22

INVITATION FOR BIDS

The Town of Mapleford, acting through its Board of Public Works (the Owner), invites sealed bids for the Elm Street and Oak Avenue Water Main Replacement, Contract No. W-2026-04, in Mapleford, Massachusetts.

Sealed bids will be received at the Office of the DPW Director, 40 Center Street, Mapleford, MA until 11:00 AM on Thursday, November 19, 2026, at which time they will be publicly opened and read aloud.

The Work consists of replacing approximately 4,850 linear feet of existing 6-inch cast iron water main on Elm Street and Oak Avenue with 12-inch and 8-inch ductile iron water main, together with new gate valves, fire hydrants, water services, temporary water, trench pavement and final paving.

A pre-bid conference will be held at 10:00 AM on Tuesday, November 3, 2026 at the DPW Garage, 12 Mill Road, Mapleford. Attendance is not mandatory.

Each bid must be accompanied by bid security in the amount of five percent (5%) of the value of the bid, in the form of a bid bond, certified check, or treasurer's or cashier's check.

This Contract is subject to M.G.L. Chapter 30, Section 39M and to the Massachusetts prevailing wage law, M.G.L. Chapter 149, Sections 26 to 27H. The Owner reserves the right to reject any or all bids.

INSTRUCTIONS TO BIDDERS

1. Bids shall be submitted on the Bid Form furnished in these Contract Documents. Unit prices shall be written in both words and figures. In case of a discrepancy, the unit price written in words governs.

2. Addenda will be issued to all plan holders of record. Each Bidder shall acknowledge all addenda on the Bid Form.

3. Award will be made to the lowest responsible and eligible bidder on the basis of the Total Base Bid. The Owner may award any or all Bid Alternates.

INSTRUCTIONS TO BIDDERS (continued)

4. The successful Bidder shall furnish a performance bond and a labor and materials payment bond, each in the amount of one hundred percent (100%) of the Contract Price, issued by a surety licensed in Massachusetts.

5. Bidders shall examine the site and the Contract Documents. Quantities shown on the Bid Form are estimates for comparing bids only; payment will be made for actual quantities installed.

BID FORM

Contract No. W-2026-04. The undersigned proposes to perform the Work at the following unit prices. Unit prices in words and figures.

Item No.	Est. Quantity	Unit	Item Description	Unit Price	Total
1	1	LS	Mobilization and Demobilization, not to exceed 3% of Total Base Bid		
2	60,000	$	Police Details (Allowance)		
3	1	LS	Traffic Management Plan and Temporary Signage		
4	3,120	LF	12-inch Ductile Iron Water Main, Class 52, including fittings		
5	1,730	LF	8-inch Ductile Iron Water Main, Class 52, including fittings		
6	180	LF	6-inch Ductile Iron Hydrant Branch		
7	9	EA	12-inch Gate Valve and Box		
8	7	EA	8-inch Gate Valve and Box		
9	12	EA	Fire Hydrant Assembly, complete		
10	64	EA	1-inch Copper Water Service, Main to Curb Stop		
11	1,150	LF	1-inch Copper Water Service, Curb Stop to House		
12	6	EA	Cut and Cap Existing Water Main		
13	1	LS	Temporary Water Service, complete		
14	20	EA	Test Pits for Existing Utilities		
15	150	CY	Rock Excavation and Disposal		
16	1	LS	Dewatering		

BID FORM (continued)

17	900	CY	Gravel Borrow for Trench Backfill		
18	200	TON	Disposal of Contaminated Soil (Allowance)		
19	2,450	SY	Temporary Trench Pavement, 3-inch		
20	2,450	SY	Permanent Trench Pavement, 4-inch HMA		
21	9,800	SY	Pavement Milling and 1.5-inch Overlay, curb to curb		
22	320	LF	Granite Curb Reset		
23	1,100	SY	Loam and Seed		
24	1	LS	Pressure Testing, Disinfection and Flushing		

TOTAL BASE BID (Items 1 through 24): _____ Dollars ($_____)

BID FORM - BID ALTERNATES

Bid Alternates are not part of the Total Base Bid.

A-1 420 LF Replace 2-inch Galvanized Main on Birch Lane with 8-inch DI

A-2 2 EA Additional Hydrant Assembly

Acknowledge Addenda: No. ____ No. ____

AGREEMENT

This Agreement is made between the Town of Mapleford (the Owner) and the Contractor named below for the Elm Street and Oak Avenue Water Main Replacement. The Contractor shall complete the Work in accordance with the Contract Documents for the unit prices stated in the Bid Form.

GENERAL CONDITIONS

The Contractor shall furnish all labor, materials, equipment and services necessary to complete the Work in accordance with the Contract Documents. The Engineer shall decide all questions about the quality and acceptability of materials furnished and work performed. The Contractor shall keep on the site a competent superintendent during the progress of the Work. Shop drawings shall be submitted in time to allow review without delay to the Work. The Contractor shall protect all existing improvements and restore any damage at no additional cost to the Owner.

Differing site conditions: if the Contractor finds subsurface conditions at the site materially different from those shown in the Contract Documents, the Contractor shall notify the Engineer in writing before disturbing them, and an equitable adjustment may be made.

GENERAL CONDITIONS (continued)

Payment: the Owner shall pay the Contractor within thirty (30) days after approval of each monthly application for payment, less retainage as provided in the Supplementary Conditions.

The Contractor shall furnish all labor, materials, equipment and services necessary to complete the Work in accordance with the Contract Documents. The Engineer shall decide all questions about the quality and acceptability of materials furnished and work performed. The Contractor shall keep on the site a competent superintendent during the progress of the Work. Shop drawings shall be submitted in time to allow review without delay to the Work. The Contractor shall protect all existing improvements and restore any damage at no additional cost to the Owner.

SUPPLEMENTARY CONDITIONS

SC-1 Contract Time. The Contractor shall substantially complete the Work within two hundred ten (210) consecutive calendar days from the date of the Notice to Proceed.

SC-2 Liquidated Damages. For each calendar day that the Work remains incomplete after the Contract Time, the Contractor shall pay the Owner liquidated damages of One Thousand Five Hundred Dollars ($1,500.00) per calendar day.

SC-3 Retainage. The Owner will retain five percent (5%) of each progress payment until substantial completion.

SC-4 Working Hours. Work shall be performed between 7:00 AM and 5:00 PM, Monday through Friday. No work is allowed on weekends or legal holidays without written approval of the Owner.

SUPPLEMENTARY CONDITIONS (continued)

SC-5 Night Work. Work within the Route 110 intersection shall be performed at night between 9:00 PM and 5:00 AM. Only one lane of Route 110 may be closed at any time.

SC-6 Police Details. Uniformed police officers are required for all work within public ways. Police details will be paid under the Police Details allowance item.

SC-7 Paving Season. No permanent trench pavement shall be placed after November 15 or before April 15 without the written approval of the Engineer.

SC-8 Subsurface Conditions. The Contractor shall make its own investigation of subsurface conditions. No claim for additional compensation will be allowed for rock, ledge or boulders encountered in the trench.

SUPPLEMENTARY CONDITIONS (continued)

SC-9 Insurance. In addition to the limits in the General Conditions, the Contractor shall carry umbrella liability insurance of not less than $5,000,000 per occurrence, naming the Town of Mapleford as an additional insured.

SC-10 Utilities. The locations of existing utilities shown on the Drawings are approximate. The Contractor shall excavate test pits to locate utilities before laying pipe.

PREVAILING WAGE RATES

The Massachusetts prevailing wage rate schedule issued for this project applies to all work. The Contractor shall submit certified weekly payrolls to the Owner. Apprentices must be registered with the Division of Apprentice Standards.

SECTION 31 23 00 - EXCAVATION AND FILL

1.01 Rock Excavation. Rock excavation is paid at the unit price bid for Item 15, measured in cubic yards within the pay limits shown on the Drawings.

1.02 Dewatering. Groundwater is expected near Station 12+00 to 18+00. The Contractor shall keep excavations free of water and shall discharge only through a sediment control device.

1.03 Compaction. Trench backfill shall be compacted to at least 95 percent of maximum dry density. The Contractor shall pay for one compaction test for every 200 linear feet of trench.

SECTION 31 23 00 - EXCAVATION AND FILL (continued)

The Contractor shall furnish all labor, materials, equipment and services necessary to complete the Work in accordance with the Contract Documents. The Engineer shall decide all questions about the quality and acceptability of materials furnished and work performed. The Contractor shall keep on the site a competent superintendent during the progress of the Work. Shop drawings shall be submitted in time to allow review without delay to the Work. The Contractor shall protect all existing improvements and restore any damage at no additional cost to the Owner.

SECTION 33 11 00 - WATER UTILITY DISTRIBUTION PIPING

3.01 Pressure Test. Each section of new main shall be pressure tested at 150 psi for two (2) hours. Leakage shall not exceed the allowable amount in AWWA C600.

3.02 Disinfection. New mains shall be disinfected in accordance with AWWA C651. Two consecutive sets of bacteriological samples taken 24 hours apart must pass before the main is placed in service.

3.03 Ductile iron pipe shall be Class 52, cement lined, with push-on joints, conforming to AWWA C151.

SECTION 02 61 00 - CONTAMINATED SOIL

1.01 Soil testing at three locations on Oak Avenue found petroleum compounds above reportable concentrations. Excavated soil in these areas shall be stockpiled, tested and disposed of at a licensed facility. Disposal is paid under the allowance in Item 18.

SECTION 34 71 13 - TRAFFIC CONTROL

1.01 The Contractor shall maintain access for residents and emergency vehicles at all times. Detours require the approval of the Mapleford Police Department at least seven (7) days in advance.

SECTION 34 71 13 - TRAFFIC CONTROL (continued)

The Contractor shall furnish all labor, materials, equipment and services necessary to complete the Work in accordance with the Contract Documents. The Engineer shall decide all questions about the quality and acceptability of materials furnished and work performed. The Contractor shall keep on the site a competent superintendent during the progress of the Work. Shop drawings shall be submitted in time to allow review without delay to the Work. The Contractor shall protect all existing improvements and restore any damage at no additional cost to the Owner.

LIST OF DRAWINGS

G-1 Cover Sheet

G-2 General Notes

C-1 Elm Street Plan and Profile Sta 0+00 to 12+00

C-2 Elm Street Plan and Profile Sta 12+00 to 24+00

C-3 Oak Avenue Plan

C-4 Details